

इन्दिरा गांधी राष्ट्रीय मानव संग्रहालय,
पोस्ट बैग नं. 2 शामला हिल्स,
भोपाल-462013

क्रमांक : -F.10-13/07-Constt
दिनांक :- 27/01/2025

दूरभाष- 2660667

सेवा में,

मेसर्स,

विषय: - संग्रहालय परिसर में जनजातीय पर्यावास क्षेत्र की सड़क मरम्मत कार्य हेतु निविदा।

महोदय,

1. पिछले पृष्ठ पर जिस कार्य का उल्लेख किया गया है उस कार्य को इस संग्रहालय द्वारा कराये जाने का प्रस्ताव है। यदि आप इस कार्य को कर सकने की स्थिति में हो तो आपसे अनुरोध है कि आप इस कार्य के लिये अपनी अनुमानित लागत से परसेंटेज नीचे / उपर की दरें बन्द लिफाफे में भेजें।
2. इस कार्य की दरें सील बंद लिफाफे में जमा करने की अंतिम तिथि 30/01/2025 है। निर्धारित तारीख के पश्चात प्राप्त दरों को मंजूर नहीं किया जायेगा।
3. कार्य की बनावट, उनकी कोटि आदि के पूरे ब्यौरे का उल्लेख इन दरों में होना चाहिये।
4. अनुमानित लागत से प्रतिशत नीचे / उपर का मूल्य उद्धृत की जाये। उद्धृत मूल्य में समस्त कर या अन्य अधिभार आदि समाहित किया जाये। सामग्री संग्रहालय परिसर के स्टोर तक रखने का मालभाड़ा दुलाई चढ़ाई एवं उतरने का खर्च दरों में शामिल होगा जिसका कोई अतिरिक्त राशी देय नहीं होगी।
5. निदेशक, राष्ट्रीय मानव संग्रहालय को यह अधिकार है कि वे बिना कोई कारण बतलाये दरें नामंजूर कर सकते हैं और निम्नतम से इतर दरें स्वीकृत कर सकते हैं।
6. इसमें उल्लेखित मात्रा उपयुक्त है आर्डर देते समय वास्तविक आवश्यकताओं के अनुसार इनकी मात्रा घटाई/बढ़ाई जा सकती है। कार्य का भुगतान कार्य पूर्ण होने पर मापन तथा गुणवत्ता की जाँच के उपरांत किया जायेगा।
7. दरें मुहरबंद लिफाफे में निम्न हस्ताक्षरी के नाम से प्रेषित की जाये कार्यालय संदर्भ संख्या F.10-07/15-Constt तारीख 27/01/2025 को दर देय है, तथा "संग्रहालय परिसर में जनजातीय पर्यावास क्षेत्र की सड़क मरम्मत कार्य हेतु निविदा" का उल्लेख दर से संबंधित लिफाफे के ऊपर आवष्यक रूप में अंकित किया जाना चाहिये।

भवदीय

सूर्य कुमार पांडे
(डा. एस.के.पाण्डेय)
कार्यालय अध्यक्ष

निम्नलिखित कार्य सम्पन्न किये जाने हैं:

S.No.	Item	Unit	Qty	Rate	Amount
1	Scarifying Existing Granular Surface to a 50 mm by Manual Means Scarifying the existing granular road surface to a depth of 50 mm and disposal of scarified material within all lifts and leads upto 1000 metres.	sqm	1155		
2	Water Bound Macadam Providing, laying, spreading and compacting stone aggregates of specific sizes to water bound macadam specification including spreading in uniform thickness, hand packing, rolling with vibratory roller 8-10 tonnes in stages to proper grade and camber, applying and brooming requisite type of screening/ binding Materials to fill up the interstices of coarse aggregate, watering and compacting to the required density as per clause 404 of specification. (ii) Grading- II (53 to 22.4mm) (a) Using Screening Type-B (11.2mm Agg.)	Cum	300		
	TOTAL				
	Add GST				
	Grand Total in Figures Rs				
	Grand Total in Words Rs				

Terms & Condition: -

1. The work shall be executed as per CPWD specification 2023 (Volume I&II) with upto date correction slips.
2. The rates shall include all leads, lifts and transportation charges of materials. The contractor shall be responsible to pay all the taxes as required and nothing shall be reimbursed by the department.
3. During execution of work, the required co-ordination is necessary with the departmental Security Staff for the safety of the IGRMS.
4. Nothing shall be paid as extra, except the quoted rates given and approved by the competent authority for the different agreement items.



5. Quantities shown in BOQ may increase or decrease. The payment will be made after actual measurement of work and satisfactory complete of work.
6. In case of any dispute, the decision of the Director, IGRMS, Bhopal shall be final and binding on the agency.
7. Time allowed for completion of work is 15 days from date of work order.
8. The working space and electrical connection & water supply will be provided free of cost in IGRMS campus for facilitating early completion of works.

आयकर नम्बर (पेन) का घोषणा पत्र :

बैंक खाता नम्बर :		
आयकर नम्बर (चूछ):		
बैंक का नाम:		
बैंक का आई.एफ.एस कोड:		

ठेकेदार/सप्लायर के हस्ताक्षर

