

Indira Gandhi Rashtriya Manav Sangrahalaya
Post Bag No. 2, Shyamla Hills,
Bhopal – 462002

Ref No.: F.10-10/07-Constt
Date: 14/01/2026

Notice Board (IGRMS)

To,

Subject: Quotation enquiry for Renovation work of modelling section shed near charaivitti at IGRMS Bhopal.

Sir,

1. The work mentioned on the next pages is proposed to be carried out by this department. If you are in a position to execute this work, you are requested to submit your rates for the same in a sealed envelope.
2. The last date for submission of rates in a sealed envelope is **21/01/2026**. Rates received after the prescribed date will not be accepted.
3. (If differ) Complete details of the nature of work, specifications, category, etc., must be clearly specified in your letter.
4. The rate should be quoted per unit. Wherever net product price, sales tax, or any other surcharge is charged additionally, the same should be specifically mentioned in the rates. The rates shall be inclusive of freight, transportation, loading and unloading charges for delivering the material up to the site within the museum premises. No additional payment shall be made on this account.
5. The Director, Indira Gandhi Rashtriya Manav Sangrahalaya, reserves the right to reject any or all rates without assigning any reason and may accept rates other than the lowest.
6. The quantities mentioned are tentative. At the time of placing the order, the quantities may be increased or decreased as per actual requirements.
7. The total sum of the quoted rates (Grand Total Amount) shall be considered as the final amount, and the lowest tender will be determined on that basis only.
8. The rates should be sent in a sealed envelope addressed to the undersigned, quoting Office Ref No. **F.10-10/07-Const**, dated **14/01/2026**. The envelope must clearly bear the inscription: "Renovation work of modelling section shed near charaivitti at IGRMS Bhopal."
9. The work site may be inspected during office hours.

Yours sincerely,


(Dr. P. Shankar Rao)
Administrative Officer

Description of work to be carried out

Item No.	Description	Qty.	Unit	Rate	Amt.
1	Dismantling roofing including ridges, hips, valleys and gutters etc., and stacking the material within 50 metres lead of: Asbestos Cement sheet	241.80	sqm		
2	Demolishing thatch roofing including mats, bamboo, jaffari etc. complete including stacking of serviceable material and disposal of unserviceable material within 50 metres lead.	85.00	sqm		
3	Demolishing brick work manually/ by mechanical means including stacking of serviceable material and disposal of unserviceable material within 50 metres lead as per direction of Engineer-in-charge. : In cement mortar	1.00	cum		
4	Providing and laying cement concrete in retaining walls, return walls, walls (any thickness) including attached pilasters, columns, piers, abutments, pillars, posts, struts, buttresses, string or lacing courses, parapets, coping, bed blocks, anchor blocks, plain window sills, fillets, sunken floor etc., up to floor five level, excluding the cost of centering, shuttering and finishing: 1:2:4 (1 Cement : 2 coarse sand (zone-III) including manufactured sand derived from Recycled Concrete Aggregate (RCA) upto 25% : 4 graded stone aggregate 20 mm nominal size including Recycled Concrete Aggregate (RCA) upto 25%).	1.00	cum		
5	Centering and shuttering including strutting, propping etc. and removal of form work for : Retaining walls, return walls, walls (any thickness) including attached pilasters, buttresses, plinth and string courses fillets, kerbs and steps etc.	5.00	sqm		
6	12 mm cement plaster of mix : 1:6 (1 cement: 6 fine sand)	15.00	sqm		



7	Steel work in built up tubular (round, square or rectangular hollow tubes etc.) trusses etc., including cutting, hoisting, fixing in position and applying a priming coat of approved steel primer, including welding and bolted with special shaped washers etc. complete. : Hot finished welded type tubes	200.00	kg		
8	Providing and fixing precoated galvanised iron profile sheets (size, shape and pitch of corrugation as approved by Engineer-in-Charge) of total coated thickness 0.50 mm (base metal of minimum 0.45 mm thickness with total coating thickness of 0.05mm) with zinc coating 120 grams per sqm as per IS: 277, in 240 mpa steel grade, 5-7 microns epoxy primer on both side of the sheet and polyester top coat 15-18 microns. Sheet should have protective guard film of 25 microns minimum to avoid scratches during transportation and should be supplied in single length upto 12 metre or as desired by Engineer-in-charge. The sheet shall be fixed using self drilling /self tapping screws of size (5.5x 55 mm) with EPDM seal, complete upto any pitch in horizontal/ vertical or curved surfaces, excluding the cost of purlins, rafters and trusses and including cutting to size and shape wherever required. : Note: Colour approved by IGRMS	241.80	sqm		
9	Providing and fixing precoated galvanised steel sheet roofing accessories of total coated thickness 0.50 mm (base metal of minimum 0.45 mm thickness with total coating thickness of 0.05 mm) with Zinc coating 120 gram per sqm as per IS: 277, in 240 mpa steel grade, 5-7 microns epoxy primer on both side of the sheet and polyester top coat 15-18 microns using self drilling/ self tapping screws complete : Note: Colour approved by IGRMS				
9a	Ridges plain (500 - 600mm)	15.50	metre		
9b	Gutter (600 mm over all girth)	15.60	metre		



10	Structural steel work in single section, fixed with or without connecting plate, including cutting, hoisting, fixing in position and applying a priming coat of approved steel primer all complete.	215.00	kg		
11	Applying priming coat: With ready mixed red oxide zinc chromate primer of approved brand and manufacture on steel galvanised iron/ steel works. After removing of old paint & loose rust etc. with wire brush / sand paper.	103.27	sqm		
12	Painting with synthetic enamel paint of approved brand and manufacture of required colour to give an even shade : Two or more coats on new work over an under coat of suitable shade with ordinary paint of approved brand and manufacture	103.27	sqm		
13	Providing and applying white cement based putty of average thickness 1 mm, of approved brand and manufacturer, over the plastered wall surface to prepare the surface even and smooth complete.	132.57	sqm		
14	Applying priming coats with primer of approved brand and manufacture, having low VOC (Volatile Organic Compound) content. : With water thinnable cement primer on wall surface having VOC content less than 50 grams/litre	265.15	sqm		
15	Distempering with 1st quality acrylic distemper (ready mixed) having VOC (Volatile Organic Compound) content less than 50 gram/ litre, of approved brand and manufacturer including applying additional coats wherever required to achieve even shade and colour : Old work (one or more coats)	117.48	sqm		

16	Finishing walls with Acrylic Smooth exterior paint of required shade : Old work (Two or more coat applied @ 1.67 ltr/ 10 sqm) on existing cement paint surface	117.48	sqm		
	Total				
	Add GST if any				
	Total estimated cost in figures Rs.				
	Total estimated cost in words Rs.				

Terms & Condition: -

1. The rates shall include all leads, lifts and transportation charges. The contractor shall be responsible to pay all the taxes as required and nothing shall be reimbursed by the department.
2. During execution of work, the required co-ordination is necessary with the departmental Security Staff for the safety of the IGRMS.
3. Nothing shall be paid as extra, except the quoted rates given and approved by the competent authority for the different agreement items.
4. The payment will be made after actual measurement of work and satisfactory complete of work.
5. In case of any dispute, the decision of the Director, IGRMS, Bhopal shall be final and binding on the agency.
6. Time allowed for completion of work is 45 days from date of work order.
7. Clearing of Spilled paint and debris should be done in co-ordination with site in charge.

Banking details: -

Account number		
PAN number		
Name of Bank		
IFSC		

Signature of contractor

